Description 4.500 acre parcel

Being a part of Fractional Section 3, T-14 N, R-11 W, Paint Township, Holmes County, Ohio, also known as part of the lands conveyed to Pauline R. Kasserman, Trustee in Official Record vol. 226 page 2361, PN 1500153000.

Described as follows:

Commencing at a 5/8 inch rebar found marking the northwest corner of Fractional Section 3, thence S 89 degrees 36' 29" E 2671.04 feet along the section line to a 5/8 inch rebar found marking the southwest corner of the southeast quarter of Section 34, thence S 89 degrees 59 05" E 620.81 feet along the section line to a 5/8 inch rebar found, thence S 03 degrees 50' 14" E 333.23 feet along Trustees Longenecker Mennonite Church's (D.V. 161 page 319) west line to a 5/8 inch rebar found, thence N 89 degrees 30' 56" E 498.40 feet along said Trustees Longenecker Mennonite Church's south line to a point in the center of C.R. 186, thence S 39 degrees 39' 45" E 633.56 feet along the centerline of C.R. 186 to a point, thence S 82 degrees 13' 40" W 885.72 feet along Ronald L. Scheufler and Priscilla Lynn Scheufler's (O.R. 181 page 2931) north line to a 5/8 inch rebar found, thence S 00 degrees 55' 35" E 290.83 feet along said Scheufler's west line to a point in the center of T.R. 670, thence S 86 degrees 34' 44" W 50.05 feet along the centerline of T.R. 670 to a point the TRUE POINT OF BEGINNING, witnessed by an iron pin set S 00 degrees 55' 35" E 21.08 feet.

thence with the following FOUR (4) COURSES:

- 1) S 00 degrees 55' 35" E 765.38 feet through the lands of said Kasserman to an iron pin set;
- 2) S 89 degrees 04' 25" W 258.01 feet through the lands of said Kasserman to an iron pin set:
- 3) N 00 degrees 55' 35" W 754.13 feet through the lands of said Kasserman to a point in the center of T.R. 670, witnessed by an iron pin set S 00 degrees 55' 35" E 26.51
- 4) N 86 degrees 34' 44" E 258.25 feet along the centerline of T.R. 670 to the TRUE POINT OF BEGINNING.

This parcel contains 4.500 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

19 See Holmes County Plat Book___ 4241 ., page_ This survey made and description prepared by Donald C. Baker, P.S. 6938. October 5, 2020

Baker OF OF

ATE OF ON

DONALD

BAKER 6938

P.S. 6938

Parcel Number: 1500153009

FILE DESCRIPTION

Holmes County Map Office

11/30/2020