## Description 16.929 acre parcel

Being a part of the northeast quarter of Section 31, Paint Township, T-15 N, R-11 W, Holmes County, Ohio, also known as part of the lands conveyed to John R. Schlabach and Mary Schlabach in Deed vol. 253 page 343, PN 1500937000.

## Described as follows:

Commencing at a 5/8 inch rebar found at the intersection of T.R. 656 and C.R. 200 marking the northeast corner of the northeast quarter of Section 31, thence S 00 degrees 09' 57" E 1602.29 feet along the section line and along T.R. 656 to a point the TRUE POINT OF BEGINNING, witnessed by a 3/4 inch rod found N 87 degrees 09' 17" W 26.76 feet.

thence with the following FIFTEEN (15) COURSES:

- 1) S 00 degrees 09' 57" E 220.38 feet along the section line and along T.R. 656 to a point, witnessed by an iron pin set N 82 degrees 30' 59" W 17.42 feet;
- 2) N 82 degrees 30' 59" W 625.56 feet through the lands of said Schlabach to an iron pin set;
- 3) N 83 degrees 46' 57" W 371.63 feet through the lands of said Schlabach to an iron pin set;
- 4) N 83 degrees 46' 57" W 255.13 feet through the lands of said Schlabach to an iron pin set:
- 5) S 87 degrees 00' 46" W 156.53 feet through the lands of said Schlabach to an iron pin set;
- 6) N 71 degrees 12' 54" W 258.53 feet through the lands of said Schlabach to an iron pin set;
- 7) N 07 degrees 19' 43" E 88.56 feet through the lands of said Schlabach to an iron pin set;
- 8) N 75 degrees 18' 48" W 301.35 feet through the lands of said Schlabach to an iron pin set;
- 9) N 37 degrees 39' 44" W 221.74 feet through the lands of said Schlabach to an iron pin set;
- 10) N 05 degrees 02' 01" E 248.82 feet through the lands of said Schlabach to an iron pin set on Aden Schlabach, Barbara Schlabach, Tim Schlabach and Ann Schlabach's (O.R. 259 page 1125) south line;

- 11) N 89 degrees 22' 48" E 834.31 feet along said Aden Schlabach, Barbara Schlabach, Tim Schlabach and Ann Schlabach's south line to a 5/8 inch rebar found;
- 12) S 01 degrees 28' 14" W 223.44 feet along said Aden Schlabach, Barbara Schlabach, Tim Schlabach and Ann Schlabach's west line to a 5/8 inch rebar found;
- 13) S 86 degrees 39' 51" E 222.56 feet along said Aden Schlabach, Barbara Schlabach, Tim Schlabach and Ann Schlabach's south line to a 3/4 inch rod found;
- 14) S 00 degrees 27' 22" E 315.50 feet along Robert A. Hershberger and Linda Sue Hershberger's (D.V. 273 page 484 and O.R. 211 page 3274) west line to a 5/8 inch rebar found:
- 15) S 87 degrees 09' 17" E 985.60 feet along said Hershberger's (D.V. 273 page 484, O.R. 211 page 3274 and O.R. 211 page 3272) south line and along Mark Allen. Weaver and Elsie E. Weaver's (O.R. 211 page 3277) south line to a point on the section line and in T.R. 656 the TRUE POINT OF BEGINNING.

This parcel contains 16.929 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

See Holmes County Plat Book 19 page 4229 for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. June 29, 2020 Revised October 29, 2020

Donald C. Baker

P.S. 6938



Parcel Number: 1500937002

FILE DESCRIPTION
Holmes County Map Office

11/24/2020