Description 0.200 acre parcel

Being a part of Fractional Section 3, Paint Township, T-14 N, R-11 W, Holmes County, Ohio, also known as part of the lands conveyed to The Trustees of the Longenecker Mennonite Church in Deed vol. 161 page 319, PN 1560008000.

Described as follows:

Commencing at a 5/8 inch rebar found marking the northeast corner of Fractional Section 3, thence N 89 degrees 59' 05" W 2018.77 feet along the section line to an iron pin set the TRUE POINT OF BEGINNING.

thence with the following SIX (6) COURSES:


- 1) S 16 degrees 43' 26" E 124.11 feet along the west line of a burying ground (D.V. 5 page 471) to an iron pin set;
- 2) N 89 degrees 08' 21" E 35.46 feet along the south line of said burying ground to an iron pin set;
- 3) S 01 degrees 44' 36" E 20.90 feet through the lands of said The Trustees of the Longenecker Mennonite Church to an iron pin set;
- 4) S 88 degrees 15' 42" W 102.60 feet through the lands of said The Trustees of the Longenecker Mennonite Church to an iron pin set on Pauline R. Kasserman, Trustee's (O.R. 226 page 2361) east line;
- 5) N 03 degrees 50' 14" W 142.66 feet along said Kasserman's east line to a 5/8 inch rebar found on the section line;
- 6) S 89 degrees 59' 05" E 40.30 feet along the section line to the TRUE POINT OF **BEGINNING.**

This parcel contains 0.200 acres, but subject to all highways and easements of record. To go to adjoiner.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

See Holmes County Plat Book_ 19 4380 , page_ for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. November 27, 2020

P.S. 6938



Parcel Number: 1560008001

