Description 19.141 acre parcel

Being a part of the northeast quarter of Section 17, Prairie Township, T-13 N, R-13 W, Holmes County, Ohio, also known as part of the lands conveyed to Marty W. Schlabach and Mary Ann Schlabach in Official Record vol. 245 page 934, PN 1700324004.

Described as follows:

Beginning at a 5/8 inch rebar found marking the northeast corner of the northeast quarter of Section 17 the TRUE POINT OF BEGINNING.

thence with the following THIRTEEN (13) COURSES:

- 1) S 00 degrees 05' 56" W 1863.94 feet along the section line to a 5/8 inch rebar found;
- 2) S 49 degrees 31' 13" W 543.07 feet along William D. Troyer and Erma Sue Troyer's (O.R. 173 page 1716) west line to a point in the center of T.R. 556, witnessed by a 5/8 inch rebar found N 49 degrees 31' 13" E 24.96 feet;
- 3) N 43 degrees 15' 05" W 274.24 feet along the centerline of T.R. 556 to a point, witnessed by an iron pin set N 44 degrees 23' 40" E 10.82 feet;
- 4) N 44 degrees 23' 40" E 158.06 feet through the lands of said Schlabach to an iron pin set;
- 5) N 13 degrees 50' 52" E 525.16 feet through the lands of said Schlabach to an iron pin set:
- 6) N 18 degrees 28' 57" E 157.10 feet through the lands of said Schlabach to an iron pin set:
- 7) N 05 degrees 36' 47" W 303.43 feet through the lands of said Schlabach to an iron pin set;
- 8) N 15 degrees 41' 38" W 251.84 feet through the lands of said Schlabach to an iron pin set;
- 9) N 58 degrees 26' 11" W 149.26 feet through the lands of said Schlabach to a 5/8 inch rebar found;
- 10) N 08 degrees 14' 25" W 132.16 feet along Hipp Farms, Ltd.'s (O.R. 246 page 1069) east line to a 5/8 inch rebar found;
- 11) N 35 degrees 33' 33" E 341.91 feet along Arlin Smucker's (O.R. 254 page 785) east line to a point;
- 12) N 50 degrees 18' 40" E 169.67 feet along said Smucker's east line to a 5/8 inch rebar found:
- 13) N 65 degrees 41' 51" E 255.26 feet along said Smucker's south line to the TRUE POINT OF BEGINNING.

This parcel contains 19.141 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

See Holmes County Plat Book 19, page 3938 for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. October 1, 2019

Donald C. Baker

P.S. 6938

DONALD

BAKER
6938

O/STERE

O/ONAL SURING

Parcel Number: 1700324007

FILE DESCRIPTION
Holmes County Map Office
11/25/2019