

Description 20.858 acre parcel

Being part of the northeast quarter of Section 18, T-13 N, R-13 W, Prairie Township, Holmes County, Ohio, also known as part of the lands conveyed to Atlee M. Troyer and Fannie Mae Troyer in O.R. 293 page 5059, PN 1700384007 .

Described as follows:

Beginning at a 5/8 inch rebar found marking the northeast corner of the northeast quarter of Section 18 the TRUE POINT OF BEGINNING.

thence with the following FOURTEEN (14) COURSES:

- 1) S 00 degrees 07' 56" E 612.01 feet along the section line to an iron pin set;
- 2) S 51 degrees 08' 26" W 735.46 feet through the lands of said Troyer to an iron pin set;
- 3) S 18 degrees 21' 25" W 554.86 feet through the lands of said Troyer to an iron pin set;
- 4) S 17 degrees 03' 58" E 58.73 feet through the lands of said Troyer to an iron pin set;
- 5) S 23 degrees 24' 51" E 114.81 feet through the lands of said Troyer to an iron pin set;
- 6) S 01 degree 24' 50" W 145.45 feet through the lands of said Troyer to a point in the center of T.R. 555, witnessed by an iron pin set N 01 degree 24' 50" E 38.22 feet;
- 7) N 50 degrees 07' 02" W 74.28 feet along the centerline of T.R. 555 to a R.R. spike found;
- 8) N 57 degrees 24' 27" W 94.00 feet along the centerline of T.R. 555 to a point;
- 9) N 44 degrees 57' 14" W 79.46 feet along the centerline of T.R. 555 to a point;
- 10) N 35 degrees 22' 55" W 138.00 feet along the centerline of T.R. 555 to a point;
- 11) N 37 degrees 06' 01" W 93.57 feet along the centerline of T.R. 555 to a point;
- 12) N 49 degrees 07' 36" W 173.85 feet along the centerline of T.R. 555 to a point;
- 13) N 34 degrees 38' 38" W 393.29 feet along the centerline of T.R. 555 to a point, witnessed by an iron pin set N 50 degrees 32' 35" E 27.39 feet;
- 14) N 50 degrees 32' 35" E 1774.99 feet through the lands of said Troyer to the TRUE POINT OF BEGINNING.


This parcel contains 20.858 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83,
2011 adjustment.

See Holmes County Plat Book 19 page 5687 for survey.
This survey made and description prepared by Donald C. Baker, P.S. 6938.
October 14, 2025


Donald C. Baker P.S. 6938



PPN: 1700384014

FILE DESCRIPTION
Holmes County Map Office
10/31/2025