

**Address:** 5434 TR 377, Millersburg, OH 44654 **Phone:** 330.231.0497

**Description:** 2.500 Acres

Being part of the Southeast Quarter of Section 22, Richland Township, T-8 N, R-9 W, Holmes County, Ohio, also known as part of the lands conveyed to Rick G. and Linda M. Hawkins in Deed Vol. 262 Page 347, PPN 2100329000.

## Described as follows:

Commencing at 5/8 inch rebar found marking the northeast corner of the southeast quarter of section 22, thence S 05 degrees 19'00" W a distance of 135.66 feet along the section line to a railroad spike found in the centerline of U.S. 62, thence N 81 degrees 26'25"W a distance of 274.27 feet along the south line of Stewart and Shirley Sommers (O.R. Vol. 176 Page 588) and centerline of said road to a point marking the TRUE PLACE OF BEGINNING;

Thence with the following FIVE (5) COURSES;

- 1. S 27 degrees 45'01" W a distance of 239.50 feet through the lands of said Rick G. and Linda M. Hawkins to an iron pin set and passing through an iron pin set at a distance of 43.26 feet;
- 2. S 88 degrees 56'35" W a distance of 155.06 feet through the lands of said Rick G. and Linda M. Hawkins to an iron pin set;
- 3. N 64 degrees00'42" W a distance of 400.00 feet through the lands of said Rick G. and Linda M. Hawkins to a point in the centerline of Township Road 26 witnessed by an iron pin set S 64 degrees 00'42"E a distance of 18.69 feet;
- 4. N 57 degrees08'56" E a distance of 200.00 feet along the east line of Joseph E. Gooding and Cheryl L. Gooding (Deed Vol. 275 Page 608) and the centerline of said road to a railroad spike found;
- 5. S 81 degrees26'25" E a distance of 463.25 feet along the south lines of Stewart and Shirley Sommers (O.R. Vol. 170 Page 1241 and O.R. Vol. 176 Page 588) and the centerline of U.S. 62 to the TRUE PLACE OF BEGINNING.

This parcel contains 2.500 acres and is subject to all high record.	nways, easements, and restrictions of
Bearings from Plat Vol. 2 Page 376.	
All iron pins set are 5/8-inch rebars 30 inches long with "Galbraith 8703".	a plastic identification cap marked
For survey see: Plat Book Vol. 19 Page	3855
This survey was made and description prepared by Caleba, 2019.	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
Parcel Number: 2100329001	CALEB JEROME GALBRAITH S-8703  **FG/STERED S/ONAL SURVIVIO

FILE DESCRIPTION

Holmes County Map Office 9/11/2019