

Description 64.034 acre parcel

Being part of the northeast quarter of Section 18, T-17 N, R-14 W, Ripley Township, Holmes County, Ohio, also known as part of the lands conveyed to William A. Wachtel, Trustee and Beverly Wachtel, Trustee in Official Record vol. 276 page 1400, PN 2300933000.

Described as follows:

Beginning at a R.R. spike found at the intersection of T.R. 501 and T.R. 503 marking the southeast corner of the northeast quarter of Section 18 the TRUE POINT OF BEGINNING.

thence with the following TEN (10) COURSES:

- 1) S 89 degrees 27' 00" W 822.55 feet along the quarter section line and along T.R. 503 to a point, witnessed by a 5/8 inch rod found N 01 degree 22' 07" E 15.86 feet;
- 2) N 01 degree 22' 07" E 191.04 feet along Roger L. Beauchemin, Trustee's (O.R. 279 page 603) east line to a point, witnessed by an iron pin set S 01 degree 22' 07" W 15.00 feet;
- 3) S 89 degrees 52' 18" W 296.87 feet along said Beauchemin's north line to a 5/8 inch rebar found;
- 4) N 06 degrees 02' 49" W 217.00 feet along Garrett L. Ervin and Haley M. Ervin's (O.R. 279 page 4950) east line to a 5/8 inch rebar found;
- 5) N 77 degrees 56' 32" W 210.28 feet along said Ervin's north line to an iron pin set;
- 6) N 00 degrees 49' 36" W 2202.53 feet along said Wachtel's (PN 2300933003) east line to a 5/8 inch rebar found on the section line;
- 7) N 89 degrees 56' 04" E 939.65 feet along the section line to a 5/8 inch rebar found;
- 8) S 00 degrees 39' 24" E 1511.37 feet along Dillon M. Baird and Rachil L. Baird's (O.R. 277 page 1605) west line to a 5/8 inch rebar found;
- 9) N 89 degrees 55' 56" E 399.69 feet along said Baird's south line to a point on the section line and in T.R. 501, witnessed by a 5/8 inch rebar found S 89 degrees 55' 56" W 24.37 feet;
- 10) S 00 degrees 55' 51" E 1134.87 feet along the section line and along T.R. 501 to the TRUE POINT OF BEGINNING.

This parcel contains 64.034 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book 19, page 5553 for survey.
This survey made and description prepared by Donald C. Baker, P.S. 6938.
March 20, 2025


Donald C. Baker P.S. 6938



PPN: 2300933009

FILE DESCRIPTION

Holmes County Map Office
5/19/2025