

Description 0.305 acre parcel

Being part of the northeast quarter of Section 35, T-15 N, R-12 W, Salt Creek Township, Holmes County, Ohio, also known as part of the lands conveyed to Clara Yoder in Official Record vol. 208 page 3346, PN 2400622000.

Described as follows:

Commencing at a 5/8 inch rebar found at the intersection of T.R. 613 and C.R. 77 marking the northeast corner of the northeast quarter of Section 35, thence S 00 degrees 13' 31" E 1299.47 feet along the section line and along C.R. 77 to a point the TRUE POINT OF BEGINNING, witnessed by an iron pin set N 61 degrees 06' 54" W 41.89 feet.

thence with the following SIX (6) COURSES:

- 1) S 00 degrees 13' 31" E 30.00 feet along the section line and along C.R. 77 to a point;
- 2) N 72 degrees 20' 34" W 253.93 feet along Lonnie D. Yoder and Krista J. Yoder's (O.R. 208 page 3348) north line to a point;
- 3) N 47 degrees 38' 42" W 46.00 feet along said Yoder's north line to a point;
- 4) N 44 degrees 13' 32" E 39.68 feet through the lands of said Clara Yoder to an iron pin set;
- 5) S 71 degrees 58' 19" E 141.59 feet through the lands of said Clara Yoder and along East Saltcreek Parochial School's (D.V. 203 page 354) south line to a 1/2 inch pipe found;
- 6) S 61 degrees 06' 54" E 129.65 feet along said East Saltcreek Parochial School's south line to the TRUE POINT OF BEGINNING.

This parcel contains 0.305 acres, but subject to all highways and easements of record. To go to adjoiner.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".  
Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83, 2011 adjustment.

See Holmes County Plat Book 2, page 675 for survey.  
This survey made and description prepared by Aaron L. Gerber, P.S. 8379.  
September 23, 2024



Aaron L. Gerber

P.S. 8379



PPN: 2400622002

**FILE DESCRIPTION**

Holmes County Map Office  
3/10/2026