## Description 26.301 acre parcel

Being a part of the northwest quarter of Section 9, Washington Township, T-19 N, R-15 W, Holmes County, Ohio, also known as part of the lands conveyed to John W. Stitzlein, Trustee in Official Record vol. 19 page 693, PN 2700279000.

## Described as follows:

Beginning at a 5/8 inch rebar found marking the northeast corner of the northwest quarter of Section 9 the TRUE POINT OF BEGINNING.

thence with the following SEVEN (7) COURSES:

- 1) S 00 degrees 07' 47" E 990.00 feet along the quarter section line to a stone found;
- 2) N 88 degrees 43' 42" W 998.33 feet along James Dean Humphrey and Jamie Lee Humphrey Miller's (O.R. 267 page 5191) north line to a 5/8 inch rebar found;
- 3) N 50 degrees 23' 01" W 560.58 feet along Rocky L. Heater and Tania S. Heater's (D.V. 265 page 529) north line to a R.R. spike found in the center of T.R. 464, witnessed by a 5/8 inch rebar found S 50 degrees 23' 01" E 30.00 feet;
- 4) N 48 degrees 33' 55" E 321.47 feet along the centerline of T.R. 464 to a R.R. spike found;
- 5) N 35 degrees 30' 00" E 401.67 feet along the centerline of T.R. 464 to a R.R. spike found:
- 6) N 27 degrees 19' 05" E 95.07 feet along the centerline of T.R. 464 to a R.R. spike found on the section line, witnessed by a 5/8 inch rebar found S 89 degrees 07' 48" E 30.00 feet;
- 7) S 89 degrees 07' 48" E 909.89 feet along the section line to the TRUE POINT OF BEGINNING.

This parcel contains 26.301 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Bearings from Ohio State Plane Coordinate System, north zone, N.A.D. 83.

See Holmes County P	lat Book	19	, page	4098	for survey.
This survey made and	descriptio	n prepar	ed by Aaror	ո L. Gerbe	er, P.S. 8379.
July 22, 2019					
Aaron L. Gerber	P.S. 83	79			
Munanthe	•				



Parcel Number: 2700279003