

Address: 5434 TR 377, Millersburg, OH 44654 **Phone:** 330.231.0497

Description: 2.000 Acres

Being part of the Northwest Quarter of Section 10, Salt Creek Township, T-14 N, R-12 W, Holmes County, Ohio, also known as part of the lands of Henry E. Burkholder and Verna Burkholder in Deed Vol. 230 Page 95 (PPN 3400047000).

Described as follows:

Commencing at a 5/8 inch rebar found capped "Gasbarre" marking the northwest corner of the northwest quarter of section 10, thence N 88 degrees 59'06" E a distance of 858.97 feet along the section line and along Township Road 605 to a point witnessed by a 1/2 inch pipe found S 00 degrees 27'08" W a distance of 29.19 feet being the TRUE PLACE OF BEGINNING.

Thence with the following FOUR (4) COURSES;

- 1. N 88 degrees59'06" E a distance of 213.06 feet along the section line and the centerline of said road to a point;
- 2. S 00 degrees27'08" W a distance of 409.04 feet along the west line of Henry E. Burkholder and Verna Burkholder (Deed Vol. 230 Page 95) to an iron pin set passing over a 1/2 inch pipe found at a distance of 28.89 feet;
- 3. S 88 degrees59'06" W a distance of 213.06 feet through the lands of said Henry E. Burkholder and Verna Burkholder to a iron pin set;
- **4.** N 00 degrees27'08" E a distance of 409.04 feet along the east line of Philip John Rangel II and Jewel A. Rangel (O.R. Vol. 273 Page 6349) to the TRUE PLACE OF BEGINNING.

This parcel contains 2.000 acres and is subject to all highways, easements, and restrictions of record.

Bearings from Grid North, Ohio State Plane Coordinate System, North Zone, NAD 83.

For survey see:	Plat Book Vol	19	_ Page	4595
This survey was March 12, 2021	made and descript	tion prepared	by Caleb	Jerome Galbraith P.S. 8703. on
CAR	14pm			$M^{\Pi\Pi}_{H_{I_{I_{I}}}}$
Parcel Number:	3400047001			CALEB JEROME GALBRAITH S-8703 PEGISTERED VICTORIAN CALEB JEROME GALBRAITH S-8703

FILE DESCRIPTION Holmes County Map Office 12/30/2021