## Description 2.648 acre parcel

Being a part of Lot 9, Fourth Quarter, Salt Creek Township, T-10 N, R-6 W, Holmes County, Ohio, also known as part of the lands conveyed to Crist J. Kauffman and Freda Kauffman in Official Record vol. 267 page 7020, PN 3400139005.

## Described as follows:

Commencing at a 5/8 inch rebar found in C.R. 201 marking the northwest corner of Lot 9, thence S 00 degrees 33' 28" W 450.81 feet along the lot line and along C.R. 201 to a point at the intersection of C.R. 201 and T.R. 629 the TRUE POINT OF BEGINNING, witnessed by a 5/8 inch rebar found S 54 degrees 58' 53" E 41.25 feet.

thence with the following SIX (6) COURSES:

- 1) N 84 degrees 14' 15" E 259.82 feet along the centerline of T.R. 629 to a 1/2 inch pipe found;
- 2) N 84 degrees 05' 32" E 182.79 feet along the centerline of T.R. 629 to a point, witnessed by a 5/8 inch rebar found S 00 degrees 33' 28" W 25.45 feet;
- 3) S 00 degrees 33' 28" W 330.68 feet along Raymond J. Kauffman and Esther R. Kauffman's (O.R. 30 page 257) west line to an iron pin set;
- 4) N 78 degrees 48' 59" W 255.05 feet through the lands of said Crist J. Kauffman and Freda Kauffman to an iron pin set;
- 5) N 75 degrees 31' 15" W 194.91 feet through the lands of said Crist J. Kauffman and Freda Kauffman to a point on the lot line and in C.R. 201, witnessed by an iron pin set S 75 degrees 31' 15" E 36.34 feet;
- 6) N 00 degrees 33' 28" E 187.57 feet along the lot line and along C.R. 201 to the TRUE POINT OF BEGINNING.

This parcel contains 2.648 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker Surveying LLC".

Basis of bearings from Ohio State Plane Coordinate System, North Zone, N.A.D. 83.

See Holmes County Plat Book 19, page 4106 for survey. This survey made and description prepared by Aaron L. Gerber, P.S. 8379. May 26, 2020

Aaron L. Gerber

P.S. 8379

AARON

GERBER
8379

OTSTERED

ONAL SURINING

Parcel Number: 3400139006