

**Address:** 5434 TR 377, Millersburg, OH 44654 **Phone:** 330.231.0497

**Description:** 92.269 Acres

Being part of the Northeast Quarter of Section 2, Salt Creek Township, T-14 N, R-12 W, Holmes County, Ohio, also known as part of the lands conveyed to Mose A. Hershberger and Verba Hershberger in O.R. Vol. 134 page 830, PPN 3400258000.

## Described as follows:

Commencing at a railroad spike found marking the southeast corner of the northeast quarter of section 2 the TRUE PLACE OF BEGINNING;

Thence with the following SIXTEEN (16) COURSES;

- 1. S 89 degrees 14'52" W a distance of 994.83 feet along the quarter section line and the centerline of Township Road 616 to a point;
- 2. N 01 degrees 08'40" W a distance of 349.61 feet along the east line of Albert A. and Fannie Miller (O.R. vol. 134 Page 828) to a 5/8 inch rebar found passing through a 5/8 inch rebar found capped "Baker" at a distance of 21.65 feet;
- 3. S 89 degrees 14'52" W a distance of 249.20 feet along the north line of said Albert A. and Fannie Miller to a 5/8 inch rebar found;
- 4. N 01 degrees 08'40" W a distance of 102.80 feet along the east line of Mervin J. and Lydia Ann Miller (Deed Vol. 241 Page 266) to a 5/8 inch rebar found;
- 5. S 89 degrees 21'26" W a distance of 365.02 feet along the north lines of said Mervin J. and Lydia Ann Miller and Raymond A. and Carol Miller (O.R. Vol. 149 Page 874) to a 5/8 inch rebar found;
- 6. S 00 degrees 01'20" E a distance of 196.08 feet along the west line of said Raymond A. and Carol Miller to a 5/8 inch rebar found;
- 7. S 89 degrees 20'54" W a distance of 31.00 feet along the north line of Raymond A. Miller and Carol Miller (Deed Vol. 233 Page 960) to an iron pin set;

- 8. S 89 degrees 22'52" W a distance of 181.91 feet along the north line of Andy A. Yoder Jr. and Sue Yoder (Deed Vol. 217 Page 190) to an iron pin set;
- 9. N 00 degrees 01'57" E a distance of 271.44 feet through the lands of Mose A. Hershberger and Verba Hershberger (O.R. Vol. 134 Page 830) to an iron pin set;
- 10. S 89 degrees 22'52" W a distance of 160.49 feet through the lands of said Mose A. Hershberger and Verba Hershberger to an iron pin set;
- 11. N 00 degrees 01'57" E a distance of 776.21 feet along the east line of Paul N. Troyer and Michelle E. Troyer (O.R. Vol. 233 Page 485) to a 5/8 inch rebar found capped "Baker";
- 12. N 89 degrees 13'13" E a distance of 610.50 feet along the south line of said Paul N. Troyer and Michelle E. Troyer to a 5/8 inch rebar found;
- 13. N 00 degrees 00'35" W a distance of 1353.00 feet along the east lines of said Paul N. Troyer and Michelle E. Troyer and Nancy M. Troyer, trustee (O.R. Vol. 249 Page 347) to a 5/8 inch rebar found capped "Baker";
- 14. N 89 degrees 40'03" E a distance of 1353.07 feet along the section line to a point in the center of State Route 241 and County Road 77 witnessed by an iron pin set S 89 degrees 40'03" W a distance of 19.62 feet;
- 15. S 00 degrees 01'44" W a distance of 756.54 feet along the section line and said road to a point witnessed by a 5/8 inch rebar found N 89 degrees 43'16" E a distance of 35.32 feet;
- 16. S 00 degrees 50'28" E a distance of 1892.23 feet along the section line and said road to the TRUE PLACE OF BEGINNING.

| This parcel or record. | contains 92.269 | e acres and | is subject to | all highways,  | easements,   | and restri | ctions of |
|------------------------|-----------------|-------------|---------------|----------------|--------------|------------|-----------|
| Bearings from          | m Grid North,   | Ohio State  | Plane Coord   | linate System, | , North Zone | e, NAD 8:  | 3.        |

All iron pins set are 5/8-inch rebars 30 inches long with a plastic identification cap marked "Galbraith 8703".

| For survey see: | Plat Book Vol | l. 19 | Page | 3851 |
|-----------------|---------------|-------|------|------|
| -               |               |       |      |      |

This survey was made and description prepared by Caleb Jerome Galbraith P.S. 8703. on July 6, 2019.

CM HW

CALEB
JEROME
GALBRAITH
S-8703

\*\*FG/STERED

\*\*SS/ONAL SURVIVIONAL SURVIVIONAL

Parcel Number: 3400258003

FILE DESCRIPTION

Holmes County Map Office 9/10/2019

3 of 3