Description 5.227 acre parcel

Being a part of the northeast quarter of Section 9, Salt Creek Township, T-14 N, R-12 W, Holmes County, Ohio, also known as part of the lands conveyed to Junior A. Stutzman and Emma A. Stutzman, trustees in Official Record vol. 149 page 397 and Official Record 149 page 399, PN 3400496000.

Described as follows:

Commencing at a 5/8 inch rebar found in T.R. 605 marking the northeast corner of the northeast quarter of Section 9, thence S 00 degrees 09' 30" W 652.87 feet along the section line to an iron pin set the TRUE POINT OF BEGINNING.

thence with the following EIGHT (8) COURSES:


- 1) S 00 degrees 09' 30" W 237.80 feet along the section line to an iron pin set;
- 2) N 59 degrees 04' 17" W 420.64 feet through the lands of said Stutzman to an iron pin set:
- 3) N 27 degrees 50' 36" W 469.27 feet through the lands of said Stutzman to a point in the center of T.R. 605, witnessed by an iron pin set S 27 degrees 50' 36" E 18.70 feet:
- 4) N 62 degrees 09' 24" E 250.70 feet along the centerline of T.R. 605 to a R.R. spike set:
- 5) N 65 degrees 46' 07" E 132.88 feet along the centerline of T.R. 605 to a point;
- 6) N 71 degrees 49' 18" E 104.80 feet along the centerline of T.R. 605 to a point, witnessed by an iron pin set S 00 degrees 09' 30" W 19.02 feet;
- 7) S 00 degrees 09' 30" W 614.38 feet through the lands of said Stutzman to an iron pin set:
- 8) N 83 degrees 11' 26" E 140.93 feet through the lands of said Stutzman to the TRUE POINT OF BEGINNING.

This parcel contains 5.227 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Bearings assumed.

19 3842 See Holmes County Plat Book___ for survey. _, page_ This survey made and description prepared by Donald C. Baker, P.S. 6938. July 17, 2019

P.S. 6938



Parcel Number: 3400496008