Description 5.062 acre parcel

Being a part of the northeast quarter of Section 9, Salt Creek Township, T-14 N; R-12 W, Holmes County, Ohio, also known as part of the lands conveyed to Junior A. Stutzman and Emma A. Stutzman, trustees in Official Record vol. 149 page 397 and Official Record 149 page 399, PN 3400496000.

Described as follows:

Beginning at a 5/8 inch rebar found in T.R. 605 marking the northeast corner of the northeast quarter of Section 9 the TRUE POINT OF BEGINNING.

thence with the following NINE (9) COURSES:

- 1) S 00 degrees 09' 30" W 22.00 feet along the section line to a point in the center of T.R. 605;
- S 76 degrees 46' 36" W 140.41 feet along the centerline of T.R. 605 to a R.R. spike set;
- 3) S 71 degrees 49' 18" W 108.27 feet along the centerline of T.R. 605 to a point;
- S 65 degrees 46' 07" W 132.88 feet along the centerline of T.R. 605 to a R.R. spike set;
- 5) S 62 degrees 09' 24" W 326.00 feet along the centerline of T.R. 605 to a point;
- 6) S 65 degrees 00' 51" W 212.45 feet along the centerline of T.R. 605 to a point, witnessed by an iron pin set N 52 degrees 22' 35" W 24.02 feet;
- 7) N 52 degrees 22' 35" W 290.16 feet through the lands of said Stutzman to an iron pin set;
- 8) N 35 degrees 29' 56" W 219.03 feet through the lands of said Stutzman to an iron pin set on the section line;
- N 88 degrees 36' 54" E 1198.97 feet along the section line to the TRUE POINT OF BEGINNING.

This parcel contains 5.062 acres, but subject to all highways and easements of record.

All iron pins set are 5/8 inch rebars with a plastic identification cap marked "Baker 6938". Bearings assumed.

See Holmes County Plat Book <u>19</u>, page <u>3842</u>, for survey. This survey made and description prepared by Donald C. Baker, P.S. 6938. July 17, 2019

Donald C. Baker P.S. 6938



Parcel Number: 3400486016

FILE DESCRIPTION Holmes County Map Office 8/28/2019