



**THOMAS E. FERGUSON**  
 AUDITOR OF STATE  
 COLUMBUS, OHIO 43216

DEPUTY AUDITORS:

JAMES A. BOLDEN  
 Administration

RICHARD G. NUSS  
 CPA  
 Auditing Division

RUSSELL ROUCH  
 Management Advising  
 Service

CERTIFICATION

I, Thomas Aquinas Burke, Supervisor, Land Office of the Auditor of State, duly authorized to perform the duties of the Auditor of State prescribed in Section 115.21 of the Ohio Revised Code, hereby certifies that the enclosed field notes and plats are true copies taken from records in our office. These plats and field notes are for the following townships in the United States Military District:

1. Range 4, Townships 8, 9 and 10
  2. Range 5, Townships 8, 9, and 10
  3. Range 6, Townships 8, 9, and 10
  4. Range 7, Townships 8, 9, and 10
  5. Range 8, Townships 8 and 9
  6. Range 9, Townships 8 and 9
- and in the Ohio River Survey
1. Range 11, Townships 14 and 15
  2. Range 12, Townships 14 and 15
  3. Range 13, Townships 13 and 14
  4. Range 14, Townships 17 and 18
  5. Range 15, Townships 19 and 20

Witness my hand and seal of the Office of the Auditor of State, at Columbus, Ohio, this Twentieth-Nine day of November in the year of Our Lord Ninteen Hundred and Eighty-Three (1983).

Thomas Aquinas Burke  
 Supervisor  
 State Land Office



ORS  
 RT  
 12 15



## Between Towns 15 &amp; 16, Range 12.

Chs. No.	
South	6 <sup>th</sup> Mile South.
10.67	A W. Oak, 17 inches diameter.
40.00	Set up $\frac{1}{2}$ mile Post, from which a Hickory, 6 ins. diam. bears S. 51 E. 12 lbs.; and a W. Oak, 12 ins. diam. bears N. 72 W. 24 links distant.
80.00	Set up Mile Post, from which a W. Oak, 15 ins. diam. bears N. 5 W. 34 lbs.; and a W. Oak, 15 ins. diam. bears South 20 links distant.
	This mile level; Timber, White Oak.
East	Tuesday, 28 <sup>th</sup> Oct. Started at the S.W. corner of T. 16, R. 12; thence East on Random Line between Towns 15 & 16, R. 12.
Ch. No.	
5.67-40	Intersect the Range line, 75 lbs. N. of the S. Corner.
West	1 <sup>st</sup> Mile West - on True Line, between T. 15 & 16, R. 12.
31.80	A W. Oak, 30 inches diameter.
40.00	Move temporary $\frac{1}{2}$ mile Post West, from which a W. Oak, 30 ins. diam. bears S. 5 E. 20 lbs.; and a Gum, 20 ins. diam. bears N. 20 E. 14 links distant.
50.50	A Run, 25 lbs. wide, runs North.
61.57	A W. Oak, 36 inches diameter.
80.00	Move temporary Mile Post West, from which a P. Oak, 16 ins. diam. bears N. 42 E. 32 links; and a Maple, 7 ins. diam. bears N. 66 W. 15 links distant.
	This mile level, rich soil; Timber, W. Oak, Dogwood, Gum, Maple.



## Between Towns 15 &amp; 16, Range 12.

Obs. Lks.

West 2<sup>d</sup> Mile West.

22.75 A W. Oak, 40 inches diameter.

40.00 More temporary  $\frac{1}{2}$  mile Post West, from which a Gum, 10 ins. diam. bears N. 50 E. 27 lks.; and a Sugar tree, 12 ins. diam. bears S. 32 E. 49 links distant.

50.00 A Water Course, 10 lks. wide, runs N. 20 E.

73.50 A W. Oak, 20 inches diameter.

74.40 A Run, 12 lks. wide, runs North.

80.00 More temporary Mile Post West, from which a W. Oak, 14 ins. diam. bears N. 64 E. 18 lks.; and a Dogwood, 7 ins. diam. bears South 30 links distant.

This mile small Ridges; Firches, W. Oak, Ash, Hickory.

West 3<sup>d</sup> Mile West.

15.00 A B. Oak, 20 inches diameter.

19.00 A W. Oak, 24 inches diameter.

40.00 More temporary  $\frac{1}{2}$  mile Post West, from which a Maple, 12 ins. diam. bears South 5 lks.; and a W. Oak, 12 ins. diam. bears N. 45 W. 16 lks. dist.

42.50 A Run, 7 lks. wide, runs N. 45 W.

50.00 A W. Oak, 50 inches diameter.

80.00 More temporary Mile Post West; from which a W. Oak, 40 ins. diam. bears S. 43 W. 19 lks.; and a Maple, 12 ins. diam. bears S. 24 E. 20 links distant.

This mile over Ridges; Firches, Oak and Dogwood.

West 4<sup>th</sup> Mile West.40.00 More temporary  $\frac{1}{2}$  mile Post West, from which a W. Oak, 40 ins. diam. bears East



Between Towns 15 & 16, Range 12.

70 links; and a Maple, 12 ins. diam. bears N. 81 W. 8 links distant.

62.00 A Water Course, 5 links, runs N. 10 W.

79.00 A Spruce, 15 inches diameter.

81.00 Move temporary Mile Post West; from which a Hickory, 12 ins. diam. bears N. 69 E. 25 links; and a Hickory, 7 ins. diam. bears N. 41 W. 4 links distant.

This mile level; rich soil; Timber, Oak, Hickory, Maple, Dogwood.

West 5<sup>th</sup> Mile West.

6.00 A Run, 3 links wide, runs N. 20 W.

8.20 A W. Oak, 20 inches diameter.

29.90 A Run, 6 links wide, runs North.

29.20 A W. Oak, 19 inches diameter.

40.00 Move temporary 1/2 mile Post; a Maple, 20 inches diameter, in the line.

60.00 A Water Course, 12 links wide, runs North.

80.00 Move temporary Mile Post West, from which a Hickory, 12 ins. diam. bears S. 28 W. 11 links; and a Cherry tree, 9 ins. diam. bears S. 41 E. 14 links distant.

This mile level, rich soil; Timber, Maple, Hickory, Ash.

West 6<sup>th</sup> Mile West.

20.00 A Run, 10 lks. wide, runs N. 50 E.

26.70 A W. Oak, 15 inches diameter.

40.00 Move temporary 1/2 mile Post West, from which a Cherry tree, 10 ins. diam. bears S. 52 W. 22 links; and an Ash, 9 ins. diam. bears N. 7 W. 3 links distant.

60.00 A Water Course, 12 links wide, runs S. 20 E.



## Between T. 15, R. 12, &amp; T. 14, R. 13

Chs. Lks.

67.45 The corner on the Range Line.  
This mile level; Alder growth, Maple and  
Birch; Timber, W. Oak.

Wednesday, 29<sup>th</sup> Oct. - Contain the Range  
Line South, between T. 15 & 14, R. 12 & 13

South 1<sup>st</sup> Mile South.

32.40 A W. Oak, 20 inches diameter.

40.00 Set up  $\frac{1}{2}$  mile Post, from which a W. Oak, 16  
ins. diam. bears N. 42 W. 9 lks.; and a W. Oak,  
13 ins. diam. bears S. 79 W. 18 links distant.

80.00 Set up Mile Post, from which an Elm, 7 ins.  
diam. bears S. 8 E. 21 links; and a Cherry tree,  
9 ins. diam. bears N. 18 E. 23 links distant.

This mile over small Ridges; Timber chiefly W. Oak.

South 2<sup>d</sup> Mile South.

.75 A Run, 6 links, runs East.

14.60 A B. Oak, ~ ins. diam. at the side of a Prairie.

36.70 Across the Prairie.

40.00 Set up  $\frac{1}{2}$  mile Post, from which a W. Oak, 12  
ins. diam. bears N. 21 E. 21 lks.; and a W. Oak,  
15 ins. diam. bears S. 44 W. 24 lks. distant.

46.00 A Run, 2 links wide, S. 50 E.

50.20 A Run, 2 links wide, runs East.

52.50 A Run, 3 links wide, runs East.

57.50 A Cherry tree, 12 inches diameter.

58.60 A Run, 3 links wide, runs N. 60 E.

70.75 A Run, 4 lks. wide, runs East.

80.00 Set up a Mile Post, from which a Hickory, 12  
ins. diam. bears N. 50 W. 21 lks.; and a Hickory,  
6 ins. diam. bears S. 63 E. 25 links distant.

First  $\frac{1}{2}$  of this mile W. Oak land and Prairie; Second  $\frac{1}{2}$   
rough, brushy, Crobbles, Thorn bushes.



## Between T. 15, R. 12, &amp; T. 14, R. 13.

Chs. Lks.

South 3<sup>d</sup> Mile South.

40.00 Set up 1/2 mile Post, from which a W. Oak,  
15 ins. diam. bears N. 1<sup>st</sup> W. 28 links; and  
a W. Oak, 20 ins. diam. bears N. 73<sup>rd</sup> W. 30  
links distant.

59.15 A B. Oak, 15 inches diameter.

80.00 Set up Mile Post, from which a W. Oak, 14  
ins. <sup>diam.</sup> bears N. 10 E. 20 links; and a Sassafras, 4  
ins. diam. bears S. 51<sup>st</sup> W. 7 links distant.

This mile ridgy W. Oak land.

South 4<sup>th</sup> Mile South.

14.00 A Run, 7 links wide, runs East.

21.00 A W. Oak, 30 inches diameter.

40.00 Set up 1/2 mile Post, from which a W. Oak,  
25 ins. diam. bears N. 54 E. 27 links; and  
a W. Oak, 15 ins. diam. bears S. 30 S. 36  
links distant.

67.80 A Spruce, 10 inches diameter.

80.00 Set up Mile Post, from which a Thorn,  
12 ins. diam. bears N. 44<sup>th</sup> W. 17 links; and  
a Crabtree, 10 ins. diam. bears N. 56 E. 16  
links distant.

First 1/2 of this mile W. Oak ridges; Second  
1/2 level Bottom; Timber, Elm, Sugar-tree,  
Crabtree, Thorn.

South 5<sup>th</sup> Mile South.

9.00 A Creek, 50 lks, runs S. 45 W.

23.40 A W. Oak, 12 inches diameter.

29.60 A Water Course, 45 lks. wide, runs West.

40.00 Set up 1/2 mile Post, from which a W. Oak, 20 ins.  
diam. bears N. 11<sup>th</sup> W. 19 lks; and a Dogwood, 8  
ins. diam. bears S. 59<sup>th</sup> W. 21 links distant.



Between T. 15, R. 12, & C. 14, R. 13.

- | Chs. & Lks.           |   |
|-----------------------|---|
| 80.00                 | Set up Mile Post, from which a B. Oak, 36 ins. diam. bears N. 34 E. 23 links; and a W. Oak, 36 ins. diam. bears S. 11 W. 10 links distant. This mile over hills; Timber, Oak. |
| South 6 <sup>th</sup> | Mile South,   |
| 25.70                 | A B. Oak, 30 inches diameter.   |
| 40.00                 | Set up 1/2 mile Post, from which a Sugar tree, 12 ins. diam. bears N. 50 W. 13 links; and a Sugar tree, 10 ins. diam. bears N. 33 E. 25 links distant.                        |
| 54.20                 | An Indian Path leads West.  |
| 59.50                 | A Run, 6 links wide, runs West.   |
| 64.60                 | A W. Oak, 40 inches diameter.   |
| 80.00                 | Set up Mile Post, from which a Dogwood, 7 ins. diam. bears N. 39 E. 18 links; and a Dogwood, 6 ins. diam. bears N. 79 W. 10 links distant.                                    |
|                       | This mile over hills; Timber, Oak and Chestnut.   |

Surveyed by  
 Thomas Clayton,  
 Deputy Surveyor.