



THOMAS E. FERGUSON
AUDITOR OF STATE
COLUMBUS, OHIO 43216

DEPUTY AUDITORS:

JAMES A. BOLDEN
Administration

RICHARD G. NUSS
CPA
Auditing Division

RUSSELL ROUCH
Management Advising
Service

CERTIFICATION

I, Thomas Aquinas Burke, Supervisor, Land Office of the Auditor of State, duly authorized to perform the duties of the Auditor of State prescribed in Section 115.21 of the Ohio Revised Code, hereby certifies that the enclosed field notes and plats are true copies taken from records in our office. These plats and field notes are for the following townships in the United States Military District:

1. Range 4, Townships 8, 9 and 10
2. Range 5, Townships 8, 9, and 10
3. Range 6, Townships 8, 9, and 10
4. Range 7, Townships 8, 9, and 10
5. Range 8, Townships 8 and 9
6. Range 9, Townships 8 and 9

and in the Ohio River Survey

1. Range 11, Townships 14 and 15
2. Range 12, Townships 14 and 15
3. Range 13, Townships 13 and 14
4. Range 14, Townships 17 and 18
5. Range 15, Townships 19 and 20

Witness my hand and seal of the Office of the Auditor of State, at Columbus, Ohio, this Twentieth-Nine day of November in the year of Our Lord Nineteen Hundred and Eighty-Three (1983).

Thomas Aquinas Burke
Supervisor
State Land Office



U S M D
R T
6 8

Chp. 22

Thursday, September 1, 1803.

North, on East Boundary of Section 21, T. 8, R. 6.

16.00 A Spring run, 6 links wide. Mill branch 10 links West
[of the line at this point]. Course S. W.

26.00 Mill branch 20 links wide. Course S 20 W.

40.50 A Spring run 50 links East of line. Course East.

46.75 A brook 6 links wide. Course S. E.

80.00 Set post corner of Sections 20 and 21, from which a
W. Oak 44 ins. diam., bears S 52 W, 17 links distant, and
a Hickory 14 ins. diam., bears N 60 E, 11 links distant.

This mile, poor stony land. Timber? Oak, Hickory and
Maple - Dogwood and Oak undergrowth.

~~It~~ In running North on the East Boundary of
Township 8 Range 6, I find the line to run N 0° 50' W,
as near as I can rectify. On the same line (the
Range line between Ranges 5 and 6) 10 miles South,
the line varies N 30' W.

West, between Sections 20 and 21.

1.50 A brook 6 links wide. Course S. E.

51.00 A run 3 links wide. Course South.

80.00 Set Temporary Section post.

This mile, generally thin soil and stony. Timber,
Oak and Hickory - Very brushy with Dogwood, Oak and
Hickory.

West, on South Boundary of Section 21.

5.00 A Spring.

6.20 A brook 20 links wide. Course South.

26.20 A brook 10 links wide. Course S. E.

28.40 A brook 3 links wide. Course N. E.

38.40 A drain. Course S. E.

39.40 Same drain. Course N. E.

40.00 Set post corner of half Sections 41 and 42, from which
an Ironwood 10 ins. diam., bears N 24 W, 5 links distant,
and a Hickory 12 ins. diam., bears N 51 E, 21 links distant.

Chs. Lks.

This half mile, poor stony land.

40.75 A drain - Course S. E.

80.00 Set post corner of Sections 21 and 22, and marked the Sections in Township 8, per plan.

This mile, thin soil, and stony - Timber, W. Oak and Hickory - Dogwood brush.

North, between Sections 21 and 22.

9.10 A Spring run - Course S. W.

20.02 A W. Oak 24 ins. diam.

75.00 A W. Oak 24 ins. diam.

77.00 A Spring run - Course N. W.

80.00 Set post corner of Sections 19, 20, 21, 22, (25 links West and 6 links South of temporary post,) from which a W. Oak 36 ins. diam. bears N 41 W, 5 links distant, and a Hickory 9 ins. diam. bears N 30 E, 24 links distant.

This mile, ridge land - Middling soil - Timber, W. Oak & Hickory, Dogwood, Oak and Hickory undergrowth.

West, between Sections 19 and 22.

5.30 A drain - Course N. W.

15.00 Same drain - Course S. W.

24.00 A run 4 links wide - Course N. W.

80.00 Set Temporary post.

This mile, first fourth, thin soil. Small W. Oak Timber - Last three-fourths on high level land - Rich soil - Large thrifty timber. W. Oak, Hickory, Gum, Ash &c. Dogwood and Spice undergrowth. Woods open and handsome.

West, on South Boundary of Section 22.

4.75 A brook 3 links wide - Course South.

6.00 A Spring - Course S. E.

20.70 A Spring run - Course South.

32.50 A run 3 links wide - Course South.

Ch. 262

40.00 Set post corner of half Sections 43 and 44, from which a Gum 12 ins. diam. bears S 51 W, 21 links distant, and a Sugar 20 ins. diam. bears S 29 W, 28 lks. distant.

40.60 A brook 8 links wide - course North.

78.85 To post corner of Sections 2 and 3, T. 7. R. 6.

80.00 Set post corner of Sections 22 and 23, from which a W. Oak 30 ins. diam. bears S 30 W, 19 links distant, and a W. Oak 20 ins. diam. bears N 44 E, 45 links distant.

This mile, open ridges - Timber, W. Oak, Hickory, Gum, Maple & Dogwood and some Spice undergrowth.

North, between Sections 22 and 23 - { Friday, Sept. 2, 1803.

10.70 A brook 10 links wide - course West.

12.93 A Hickory 12 ins. diam.

38.02 A W. Oak 15 ins. diam.

48.50 A brook 6 links wide - course West.

59.05 A W. Oak 16 ins. diam.

80.00 Set post corner of Sections 18, 19, 22, 23, 10 links North and 34 links East of Temporary post on East and West line, from which a W. Oak 28 ins. diam. bears S 57 W, 5 links distant, and a Hickory 12 ins. diam. bears N 61 E, 24 links distant.

This mile, hilly land; middling soil - Timber, Oak and Hickory, Gum and Maple - Dogwood, Hawth, Spice, Oak and Hickory, undergrowth - thick.

North, between Sections 18 and 19.

21.57 An Aspen, 12 ins. diam.

38.00 A brook 10 links wide - Course West - on edge of bottom.

51.00 Doughty's fork of Kill buck creek, 50 links wide - course S. W.

52.31 An Elm 18 ins. diam.

72.10 A Cherry 12 ins. diam. Across Thorn and Crab Apple bottom.

80.00 Set post corner of sections 12, 13, 18, 19, from which

Chs. Lks.

a W. Oak 18 ins. diam., bears N 53 W, 20 links distant,
and a W. Oak 30 ins. diam., bears S 74 E, 12 lks. distant.

This mile, first 10 Chs. on the North side hill - Rich
land - The bottom, very bushy - Soil good - Last 10 Chs
thin side hill - Timber, Oak, Hickory, Dogwood &c.

North, between Sections 12 and 13.

16.63 A W. Oak 24 ins. diam.

38.04 A W. Oak 20 ins. diam.

60.12 A W. Oak 30 ins. diam.

80.00 Set post corner of Sections 8, 9, 12, 13, from which a
W. Oak 40 ins. diam., bears N 55 E, 19 links distant, and a
Hickory 10 ins. diam., bears S 75 W, 15 links distant.

This mile, ridge land - Middling soil - Timber, Oak
and Hickory - Dogwood, Oak, Spice and Hickory under-
growth.

North, between Sections 8 and 9.

8.50 Bottom land.

13.25 A brook 12 links wide - Course West.

43.50 A run - Course S. W.

45.00 A brook 12 links wide - Course S. W.

51.10 A Maple 24 ins. diam.

57.60 A W. Oak 20 ins. diam.

58.50 A brook 12 links wide - Course S. E. Up the run.

65.00 A run - Comes from N. W.

72.50 A brook 3 links wide - Course West.

80.00 Set post corner of Sections 2, 3, 8, 9, from which a
Maple 14 ins. diam., bears N 13 E, 12 links distant, and a
W. Oak 20 ins. diam., bears S 55 W, 15 links distant.

This mile, generally near a brook. The hills on
each side, not high, but pretty rocky - Timber, Oak and
Beech. Dogwood undergrowth.

North, between Sections 2 and 3.

4.28 A W. Oak 30 ins. diam.

Ch. Lk.

18.00 A brook 4 links wide - course S. W.

29.03 A Sugar 20 ins. diam.

57.08 A W. Oak 30 ins. diam.

62.00 A drain - course S. W.

82.80 Intersected North Boundary of this Township - Set post corner of Sections 2 and 3, from which a Maple 18 ins. diam., bears S 4 N, 20 links distant, and a Maple 12 ins. diam., bears N 45 E, 14 links distant.

This mile, low open ridges - Large W. Oak timber. Some Beech, Maple and Hickory - Dogwood undergrowth. Last part of the mile stony - first part, middling soil.

West, on North Boundary of half Section 5.

3.50 A brook 3 links wide - Course South.

9.30 Fine Spring - course South.

40.10 To old section corner - Set post corner of half Section 5 T. 8, R. 6, and half Section 46, T. 9, R. 6, from which a Beech 7 ins. diam., bears N 21 E, 14 links distant, and a W. Oak 32 ins. diam., bears S 53 E, 38 links distant.

This half mile, low open ridges - Soil middling but stony - Timber, W. Oak, W. Oak, Hickory, Chestnut and Maple.

South, on random line through the Township, from the old section corner on the North Boundary - On First Mile.

51.75 A Spring run - Course East.

80.80 The length of the mile, half a mile East - Set Temporary post.

This mile, dry ridges - Timber, Oak, Hickory and much Chestnut; but little undergrowth - Soil very stony the whole mile.

South, random, on Second mile.

10.00 A brook 12 links wide - course S. W.

53.50 A Spring - Course S. E.

Chs Lks

80.00 Set temporary post.

This mile, ridge land - Lumber, Oak, Hickory, Gum, Maple and Chestnut. Dogwood, Ironwood and such like undergrowth. Soil very stony - Woods much more bushy than last mile.

South, random, on Third mile.

11.75 A Spring run - Course S. E.

22.75 A brook 15 links wide. Course West.

80.00 Set temporary post.

This mile, first half, hilly - thin soil - Lumber, Oak, Hickory, Beech, Maple and Gum - Last half of this mile on the East side of a ridge of very gradual ascent - Good soil - Lumber, Oak and Hickory - some Ash - Spice and Dogwood undergrowth.

South, random, on Fourth mile.

10.00 down rocky ridge to bottom.

13.00 A drain in bottom - Course East.

22.60 A creek 50 links wide - Course West.

27.00 across bottom.

57.50 A brook 4 links wide - Course West.

80.00 Set temporary post.

This mile, the bottom good - The upland middling. Lumber, Oak and Hickory - Dogwood and Spice undergrowth. The ridges not steep - Good farming country.

South, random, on Fifth mile.

41.50 A brook 15 links wide - Course West.

66.75 A brook 3 links wide - Course N. W.

80.05 Intersected South Boundary of this Township at old section corner [of Quarter Townships 3 and 4.]

This mile, ridge land - Middling soil - Lumber, Oak and Hickory - Dogwood and Spice undergrowth. Good farming country.

Quit for the day, September 2, 1803.

Ch. 1st 1/2nd

Saturday, September 3, 1803.

West, between half sections 36 and 45.

16.05 A W. Oak 24 ins. diam.

34.75 A drain - Course S. E.

40.40 Intersected the West Boundary 20 links North of temporary post. Set post corner of half sections 36 and 45, from which a B. Oak 12 ins. diam. bears S 36 E, 23 links distant, and a Hickory 10 ins. diam. bears N 53 E, 32 links distant.

This half mile, generally a dividing ridge. Good land - Timber, Oak and Hickory - Dogwood and Spice undergrowth.

Blazed the line between sections 19 and 22, and set post corner of half sections 37, 38, 43, 44 at the average measure, from which a Hickory 20 ins. diam. bears N 61 E, 5 links distant, and a W. Oak 14 ins. diam. bears N 14 W, 27 links distant.

North, between sections 19 and 20.

14.80 A W. Oak 30 ins. diam.

32.50 A B. Oak 30 ins. diam.

46.00 A Hickory 24 ins. diam.

60.00 A brook 6 links wide - Course NW.

63.87 A W. Oak 26 ins. diam.

80.00 Set post corner of sections 11, 12, 19, 20, from which a Gum 12 ins. diam. bears S 88 W, 16 links distant, and an Ironwood 11 ins. diam. bears N 12 E, 18 lks. distant.

This mile, ridges very brushy and stony - Timber, Oak, Hickory, Maple - Ironwood, Dogwood and Spice undergrowth.

Blazed the line between sections 20 and 21, and set post corner of half sections 39, 40, 41, 42 at average measure, from which a Maple 16 ins. diam. bears S 14 W, 7 links distant, and a Gum 12 ins. diam. bears

Ch. Lks

N 11 W, 15 links distant.

North, on East Boundary of Section 20.

33.50 A drain - Course East.

37.25 A brook 4 links wide - Course East.

69.00 A Spring run - Course N. W.

80.00 Set post corner of Sections 11 and 20, from which a
B. Oak 20 ins. diam., bears N 41 W, 18 links distant, and
a B. Oak 20 ins. diam., bears S 35 W, 24 lks. distant.This mile, poor stony and crummy ridges - Timber,
Oak, Chestnut &c.

North, on East Boundary of Section 11.

8.00 A small run - Course West.

26.20 A brook 8 links wide - Course West.

40.62 Old Section corner [of Quarter Townships 1 and 4].

50.25 A brook 6 links wide - Course West.

80.00 Set post corner of Sections 10 and 11, from which a
Chestnut 24 ins. diam., bears S 62 W, 68 links distant, and
a B. Oak 20 ins. diam., bears S 58 E, 18 links distant.This mile, poor stony land - Timber, thin - Much
Chestnut and some Hickory - Very brushy with Dogwood,
Oak, Hickory, Chestnut, Grape-vines and Green briars, &c.

West, between Sections 10 and 11.

19.00 A brook 8 links wide - Course S. W.

40.00 Set Temporary half Section post.

49.00 Soughty's fork of Killbuck creek, 40 links wide - Course
South - High ledges of rocks and Laurel, on East side.

70.20 A brook 10 links wide - Course South.

80.00 Set Temporary post.

This mile, hilly land - Timber Oak and Hickory - Very
brushy with Ironwood, Dogwood, some Spice and Laurel.

West, between Sections 11 and 20.

14.00 A run 4 links wide - Course N. W.

Ch. Sk.

66.50 A Spring run - Course North.

80.00 Intersected [North and South line] at post.

This mile, generally on the North side of a ridge - Stony soil. Timber, Oak, Hickory, some Ash, Sugar and Walnut - Spice and Dogwood undergrowth.

East, connected, between Sections 11 and 20.

Blazed the line, and set post corner of half Sections 21, 22, 39, 40, from which a B. Walnut 30 ins. diam. bears S 81 E, 14 links distant, and a B. Walnut 12 ins. diam. bears S 69 W, 25 links distant.

West, between Sections 12 and 19.

3.50 An excellent Spring - Course N. W.

10.25 A brook 6 links wide - Course N. W.

23.00 A creek 50 links wide - Course S 60 W.

66.00 A Spring - Course South.

80.00 Intersected the North and South line 8 links North of post.

This mile, mostly creek bottom, Timber, Oak - Ironwood, Hawth, Cherry & undergrowth.

West, between Sections 13 and 18.

6.88 A Maple 26 ins. diam.

40.45 Intersected West Boundary 3 links South of post. Set post corner of half Sections 25 and 36, from which a Cherry 16 ins. diam. bears S 71 E, 22 links distant, and a Hickory 12 ins. diam. bears N 10 E, 25 links distant.

This half mile, poor points of ridges - Stony soil. Timber, Oak, Maple and Hickory. Dogwood, Ironwood Hawth and Blue Beech, undergrowth.

Quit for the day, Sept. 3, 1805.

Sunday, September 4, 1805.

Blazed the line between Sections 12 and 19, and set post corner of half Sections 23, 24, 37, 38 at average

Ch. Lks

measure, from which a Crab Apple 12 ins. diam. bears
N 72 W, 5 links distant, and a W. Oak 24 ins. diam.
bears S 50 E, 38 links distant.

North, between Sections 11 and 12.

5.40 A brook 10 links wide - Course West.

10.24 A W. Oak 20 ins. diam.

25.60 A B. Walnut 18 ins. diam.

40.50 A Creek 50 links wide - Course S. W.

50.00 Across good bottom.

80.00 Intersected [East and West line] 10 links East and
20 links North of temporary post - Set post corner of
Sections 9, 10, 11, 12, from which a Maple 12 ins. diam.
bears S 85 E, 22 links distant, and a W. Oak 40 ins. diam.
bears S 57 W, 10 links distant.

This mile, the hill land middling soil - Timber,
Oak, Hickory - Much Maple - Undergrowth, Dogwood,
Spice and Ironwood.

West, between Sections 9 and 12.

54.50 A brook 6 links wide - Course N. W.

62.50 A Spring run 6 links wide - Course North.

79.88 Intersected North and South line 20 links North of post.

This mile, first half on top of ridge. Last half on
North side of ridge. Timber, Oak, Hickory, Maple,
some Ash, Dogwood, Hawth, Beech, Ironwood and some
Spice undergrowth. Soil generally pretty good for
grain and grass.

West, between Sections 8 and 13.

12.75 A brook 12 links wide - Course S. W.

13.18 A Hickory 20 ins. diam.

22.00 A Spring - Course South.

22.45 A Linn 20 ins. diam.

25.00 A drain - Course S. E.

40.28 Intersected West Boundary 12 links North of temporary

ch. 56

post. Set post corner of half Sections 16 and 25, from which a W. Oak 26 ins. diam. bears S 62 E, 42 lks. distant, and a Maple 18 ins. diam. bears S 14 W, 24 lks. distant.

This half mile, first 10 chains, descending a hill. Good soil - Then 20 chains, on north side of run bottom - Good meadow land - Last 10 chains, stony land. Side hill.

Corrected the line, between Sections 9 and 12.

Blazed the line and set post corner of half Sections 17, 18, 23, 24 at average measure, from which a Maple, 20 ins. diam. bears N 75 W, 32 links distant, and a Hickory 20 ins. diam. bears S 38 E, 31 links distant.

North, between Sections 9 and 10.

12.50 A brook 10 links wide - course S. E.

20.50 A Hickory 12 ins. diam.

35.92 A W. Oak 24 ins. diam.

44.75 A W. Oak 24 ins. diam.

62.50 A brook 6 links wide - course West.

71.00 A brook 3 links wide - course S. W.

72.60 A W. Oak 30 ins. diam.

80.00 Set post corner of Sections 1, 2, 9, 10, from which a Hickory 12 ins. diam. bears S 37 W, 3 links distant, and a W. Oak 30 ins. diam. bears S 54 E, 10 links distant.

This mile, low open ridges. Stony soil - Timber, W. Oak, Hickory, Chestnut and Maple - Dogwood undergrowth. Soil thin, but very well timbered.

Corrected between Sections 10 and 11.

Blazed the line, and set post corner of half Sections 19, 20, 21, 22 at average measure, from which a W. Oak 14 ins. diam. bears N 68 W, 26 links distant, and a Maple 20 ins. diam. bears S 73 E, 21 links distant.

North, on East Boundary of Section 10.

Ch. 11

- 14.00 A brook 4 links wide - Course West.
 30.50 A brook 4 links wide - Course S. W.
 56.50 A brook 6 links wide - Course W. High rocks. Hemlock narrows.
 63.75 A Small spring run - Course West - Hemlock.
 80.00 Set post corner of Sections 1 and 10, from which a B. Oak 12 ins. diam, bears N 15 W, 7 links distant, and a W. Oak 9 ins. diam, bears S 21 W, 30 links distant.

This mile, hilly, thin soil - Timber, W. Oak, B. Oak, Hickory &c. East quarter, bald hills - Steep Hemlock hills to the west of the line, on creek.

West, between Sections 1 and 10.

- 10.00 A creek 50 links wide - Course S. E. High Hemlock narrows on each side, and rocky.
 56.80 A drain - Course South.
 74.00 A drain - Course S. W.
 80.15 Intersected North and South line 59 links South of post.

This mile, the first 30 chains, Hemlock Hills - The remainder, poor land - Oak and Hickory timber - Dogwood undergrowth - Ridge land.

North, between Sections 1 and 2.

- 35.30 A Maple 12 ins. diam.
 40.80 A Spring run - Course S. E.
 45.94 A W. Oak 20 ins. diam.
 71.10 A brook 4 links wide - Course East.
 75.50 A drain - Course East.
 75.94 A Maple 12 ins. diam.
 78.50 A Spring - Course East.
 82.00 Intersected the North Boundary of this Township. Set post corner of Sections 1 and 2, from which a W. Oak 30 ins. diam, bears S 67 E, 29 links distant, and a Maple 12 ins. diam, bears N 41 W, 14 links distant.

This mile, poor stony ridges. Timber, Oak, Hickory.

Chs. 16.

and hickory - Dogwood undergrowth - Woods open and
handsome - Ridges not steep.

West, between Sections 2 and 9.

10.10 A brook 6 links wide - course S. W.

14.50 A drain - course S. W.

45.60 A brook 8 links wide - Course S 20 W.

41.30 A brook 3 links wide - Course S. W.

80.07 Intersected the North and South line 20 links North
of post.

This mile, open ridges - not high. Middling soil.
Timber? Oak, Hickory, Beech, Maple & Dogwood, Ironwood,
and some Spice undergrowth - Plenty of stone.

West, between Sections 3 and 8.

3.70 A brook 8 links wide - Course South.

27.00 A W. Oak 30 ins. diam.

32.35 A brook 10 links wide - Course S. W.

33.90 A W. Oak 30 ins. diam.

41.00 Intersected West Boundary of this Tract, 23 links
South of Temporary post - Set post corner of half Sect.
5 and 16, from which a W. Oak 24 ins. diam. bears
S 80 $\frac{1}{2}$ E, 48 links distant, and a Hickory 12 ins. diam. bears
S 54 W, 27 links distant.

This half mile, stony ridges - Timber? Oak, Hick-
ory, hickory and Maple - Dogwood, Ironwood &
undergrowth.

Monday, September 5, 1803.

Corrected, between Sections 2 and 9.

Placed the line and set post corner of half Sections
3, 4, 17, 18, from which a Beech 20 ins. diam. bears
N 66 $\frac{1}{2}$ W, 20 links distant, and a Beech 16 ins. diam.
bears S 55 E, 34 links distant.

Corrected, between Sections 1 and 10.

Chs. Lks

Placed the line, and set post corner of Half Sections 1, 2, 19, 20 at average measure, from which a B. Oak 15 ins. diam. bears $N 13\frac{1}{2} E$, 7 links distant, and a Hickory 12 ins. diam. bears $S 27 E$, 32 links distant.

North, on East Boundary of Section 1.

47.20 A drain - course $N. E.$

67.60 A Creek 25 links wide - Course $N. W.$

82.18 To old Township Corner. Set post, and marked per plan, from which a W. Oak 24 ins. diam. bears $S 49 W$, 18 links distant, and a W. Oak 20 ins. diam. bears $N 22 W$, 24 links distant.

This mile, poor hills - very brushy with Dogwood Oak and Hickory - Lumber, Oak and Maple, and some Hickory and Cherry. Saw near the creek.

West, on North Boundary of Section 1.

8.00 A Creek 30 links wide - Course South.

26.85 A brook 3 links wide - course $N. E.$

34.50 A drain - Course $N. E.$

40.00 Set post corner of Half Sections 1 and 2, from which a Maple 12 ins. diam. bears $S 6\frac{1}{2} W$, 33 lks. distant, and a W. Oak 40 ins. diam. bears $S 75 W$, 35 links distant.

54.50 A brook 6 links wide - course $N. W.$

72.90 A brook 3 links wide - Course $N. E.$

40.10 [Perhaps the Surveyor means 80.10]. Set post corner of Sections 2 and 3. [Perhaps Sections 1 and 2.]

This mile ridge land. Soil thin. Lumber, Oak and Hickory - Open woods - Dogwood undergrowth.

West, on North Boundary of Section 2.

40.00 Set post corner of half Sections 3 and 4, from which a Chestnut 30 ins. diam. bears $S 7\frac{1}{2} E$, 45 links distant, and a Chestnut 16 ins. diam. bears $N 22 E$, 37 lks. distant.

This half mile, open, handsome Chestnut ridges. Middling soil.

Ch. 16A

80.00 To post corner of sections 2 and 3.

This half mile, open Chestnut ridges. Soil thin
and stony & quit for the day, Sept^r. 5, 1803.

Sept^r. 5, 1803 - Lay by half a day.

Sept^r. 6, 1803. Lay by [today] - Smith sick.

Surveyed in the year 1803, by
Ebenezer Buckingham,
Deputy Surveyor.
