

No 83

Report of the Establishment of the Corner of Sections 23, 24, 25 & 26
in Township 18, Range 14, and on the Line between Holmes^{Co} & Wayne Counties.

To The Hon. Board of County Commissioners of
Holmes County, Ohio.

In obedience to your order, the undersigned
County Surveyor of Holmes County, Ohio, met Philip Markley,
County Surveyor of Wayne County, Ohio, on the 25th day of November
1887, for the purpose of establishing the corner of Sections 23,
24, 25 & 26, Township 18, Range 14 and on the line between Holmes
and Wayne Counties; and on account of inclement weather
the establishment of said corner was adjourned until the last
day of December 1887. On which date we took to our assistance
O. Hemiller and A. J. Garrett as chain carriers and O. A. Shreve^{of}
Ervin J. Shreve as flagman all of whom were duly sworn
according to law. Finding no original bearing or witness trees
to said corner nor evidences of the same we proceeded to the
north-west corner of section 26 in the above named Township
and Range, where we found one of the original witness trees
and a stone at the corner, which we found to be correctly
planted. We then extended a line from this point east
past said corner to be established and to the north east corner
of section 25 in said Township and Range, where we found
a stone marking the corner and which was undisputed.
We then extended a line from the north west corner of section 24
in Wayne County, Ohio, ^{SOUTH} to the south-west corner of section 25
in Holmes County Ohio and at the intersection of said lines
we established the corner, planted a stone, and took witnesses to the
same. All of which is shown on the plat hereto
attached and made a part of this report.
Millersburg, Ohio Dec 7, 1887.

W. S. Hanna
County Surveyor.

See Plat with notes on next page