

Description of Perkins and Smith's

Addition To the Town of Holmesville.

This addition is situated in the north middle part of the South east quarter of section three (3) in Township thirteen, in the thirteenth Range and is in the County of Holmes and is bounded as follows to wit: Beginning at a Stone post planted in the north line of said Quarter one thousand six hundred and seventy six feet west from the North East Corner thereof and which Stone post is also the North East Corner of the town of Holmesville as laid out by Peter Painter. Thence $S 1^{\circ} 08' E$ six hundred and sixty feet to a post thence $S 89^{\circ} W$ two hundred and ninety seven feet to a post in the east line of Taylor Street thence $S 1^{\circ} 08' E$ six hundred and seventeen and three tenths feet to a post. thence $N 89^{\circ} 30' E$ five hundred and four and three tenths feet to a post in the west line of the station ground of the Holmesville Station of the Cleveland, Jamesville and Cincinnati Rail Road. Thence by the same $N 8^{\circ} 19' E$ four hundred and seventy one feet to a stone post. thence $N 30^{\circ} 50' E$ on the west line of said Station ground nine hundred and sixty feet to a post in the north line of said Quarter section. Thence by the same $S 89^{\circ} W$ seven hundred and ninety four feet to the place of beginning.

Size and Description of Lots

Lots No 61, 62, 63, 64, 67, 68, 69, and 70. are each one hundred feet long, north and south by sixty three feet wide east and west. Lots No. 54, 55, 56, 57, and 58. are each one hundred and twenty six feet long north and south by sixty three feet wide east and west.

The west ^{side} of lot No 45 is one hundred and fifty one and eight tenths feet long
 " " " " " 46 " one hundred and fifty two and five tenths feet long
 " " " " " 47 " one hundred and fifty three and two tenths feet long
 " " " " " 48 " one hundred and fifty three and nine tenths feet long
 " " " " " 49 " one hundred and fifty four and six tenths feet long
 " East " " " " 49 " one hundred and fifty five and two tenths feet long
 and each sixty three feet wide east and west.

The north side of lot No 50 is one hundred and thirty five and five tenths feet long
 " " " " " 51 " one hundred and twenty two and four tenths feet long
 " South " " " " 51 " one hundred and nine and three tenths feet long

The west ends of 50 & 51 are each seventy seven and six tenths feet long north and south
 and the east ends are each seventy nine and two tenths feet on Market Street.

The north side of Lot No 52 is one hundred and seven and three tenths feet long
 " " " " " 53 " ninety six and eight tenths feet long
 " South " " " " 53 " eighty six and two tenths feet long

The west ends of 52 & 53 are each sixty three feet long north and south and the east ends are each sixty three and three quarters feet on Market Street.

Size and Description of Lots, Continued.

The north side of lot No 59 is one hundred and thirty eight and two tenths feet long
 " " " " " 60 " one hundred and twenty nine and three tenths feet long
 " South " " " " 60 " one hundred and twenty one and five tenths feet long
 North " " " " 65 " one hundred and nineteen and five tenths feet long