

115884

N. Line Lot 5, 3rd 1/4, T8N, R6W

266.30'

I.P.

986.13'

I.P. at

11.13' I.P.

West N.E. crnr  
17.88' + 968.25' = 986.13'

521° 2' E  
195.74'

REC'D: October 19, 1978

AT 4:15 O'CLOCK P.M.

RECORDED Oct. 20, 1978

T.R. 122

HOLMES CO. Plat VOL. 8 PG 325

FEE: \$ 2.00

Richard Shuman RECORDER

Deed Vol. 203  
Page 668

523° 56' E  
141.13'

528° 42' E  
126.71'

Paul Wenger

3.379 Ac. part of  
Vol. 170 Pg. 553

472.48' I.P. I.P.

485.11' Total

N 8° 27' 40" W

I.P.

1.50'

581° 32' 37" W 363.19' + 24.29'  
= 387.48'

I.P.



GRAPHIC SCALE IN FEET

Known as part of Lot 5, 3rd 1/4, T8N, R6W, of Mechanic Twp., Hol. Co., Ohio, and more fully described as follows.

Beginning at the N.E. crnr Lot 5, marked by an iron pin, thence West on the N. line to a point in T.R. 122 a distance of 986.13' to the point of beginning of the here in described parcel;

thence with T.R. 122 the following 3 courses, 521° 2' E 195.74', 523° 56' E 141.13', and 528° 42' E 126.71';

thence leaving T.R. 122 581° 32' 37" W 387.48' to an iron pin and passing an iron pin at 24.29';

thence N 8° 27' 40" W 485.11' to the N. line Lot 5 and passing iron pins at 1.50' and 473.98';

thence East on the N. line 266.30' to the place of beginning and containing 3.379 acres, but subject to all legal highways.



PLAT OF A SURVEY FOR  
MOSE C. WENGERD  
(Grantor)

Part of Lot 5, 3rd 1/4, T8N  
R6W of Mechanic Twp. Hol.  
Co., Ohio.

Robert L. Kasner P.S. 5193  
P.E. 28820