

Gata Wood Property
V180 P733

Beginning at a stone at the N.W. crnr of the
N.W. 1/4 S.W. 1/4 56, T8N, R8W of Richland Twp., Hol. Co.,
Ohio;

thence with the Range line $N4^{\circ}25'0''E$ 76.75'
to a drill hole in a rock in an old road bed on the
E. line of V200 P169 at the point of beginning;
thence leaving the Range line and with the
old road bed into V200 P169 the 8 courses to the
S. line of the Gate Wood Property: $N28^{\circ}3'40''W$
90.45' to an iron pin set, $N54^{\circ}5'40''W$ 126.99' to
an iron pin set, $N30^{\circ}36'40''W$ 184.27' to an iron
pin set, $N20^{\circ}43'40''W$ 132.20' to an iron pin
set, $N45^{\circ}20'30''W$ 93.86' to an iron pin set,
 $N56^{\circ}9'20''W$ 88.89' to an iron pin set, $N61^{\circ}$
 $15'20''W$ 231.98' to an iron pin set, and $N28^{\circ}$
 $0'34''W$ 325.95' to a above mentioned property
line and there to terminate.

Easement Restrictions for
Horger Tract
S.E. 1/4 N.E. 1/4 510
T8N R9W

1. 16' wide - 8' either side centerline.
2. Grantor retains right of use.
3. Grantor shall not be responsible for maintenance.
4. Easement specifically excludes use for overhead or underground utilities.
5. Any changes to exist in vertical alignment subject to approval of grantor.
6. Any proposed drainage structures subject to approval of grantor.
7. Any material what soever (including trees) removed from easement shall remain property of the grantor.

Robert C. Horger
V200 P169

Old Phillips Property
Chaney Tract V207 P216

Beginning at a stone at the N.W. crnr
of the N.W. 1/4 S.W. 1/4 56, T8N, R8W, of Richland Twp.,
Hol. Co., Ohio:

thence with the Range line $N4^{\circ}25'0''E$
76.75' to a drill hole in a rock in an old road
bed on the W. line of V207 P216 at the point of beginning;
thence leaving the Range line and with
old road bed into V207 P216 the following 4
courses to an iron pin set in T.R. 29:
 $520^{\circ}49'20''E$ 283.95' to an iron pin set,
 $511^{\circ}39'20''E$ 122.82' to a drill hole in a rock,
 $51^{\circ}19'50''E$ 256.04' to a drill hole in a rock,
and $58^{\circ}52'20''W$ 116.66' to above mentioned
iron pin in T.R. 29, and there to terminate.

129829



REC'D. December 31, 1981
AT 10:33 O'CLOCK P.M.
RECORDED Jan. 4, 1982
Plot VOL 9 PG. 114
Holmes Co. Ohio Fee: 6.44
Richard Brown Recorder

APPROVED BY
TAX MAP OFFICE
Date 12-31-81

Robert L. Kasner P.S. 5193
R.E. 28820

