

RICHLAND TOWNSHIP
HOLMES COUNTY, OHIO
SE QTR. SECTION 8, T-8N, R-9W

Judith A. Jacob
Linda E. Horn

I Reset This Pin
Per Kasner Rec.
Data. Fits Fence
Well

Conflicting Deeds To Ownership
Here
(Definitely Not Morris)

TR 14

Cole Excavators Inc.

CONRAIL Abandoned

389.3' rec. (Pl. 5, P. 100)
383.5' meas.

165.00'

587°46'47"E

2576.09' To R.R. Spk.

I.P. Fd.
19.63' S. Of Line

I Marked The North & West Lines With Lath & Ribbon

Sellner Called For A Stone Fd.
389.5' S. Of The Road. I Found
The Remnants Of A Fence Corner
But I Think The Stone Was
Destroyed When The Line Was
Cleared For A Power Line. I Am
Using The Fence Corner. Caution:
A New Fence Was Built About 20'
East But I Am Referring To The
Old Fence.

I Set A Railroad Spike
On Line, About 10' West Since I
Did Not Run The Section Line

Ref. To R.R. Spike:
Power Pole E. 25.3'
24" Stump N. 3'

Surveyed For James H. Morris, Owner
Deed Vol. 185, Pg. 357
& Vol 217, Pg. 595

0 100 200 300
Scale: 1" = 200 Feet

- Stone Found
- Iron Pin Fd.
- △ R.R. Spk. Set
- Iron Pin Set
- 5/8" Rebar w/ Cap
Marked "LON6-6505"

References: P.V. 5, Pg. 100
Surveys By Kasner
On Adjoining Coy &
Jacobs Properties

Bearings From
Kasner Surveys

8 8
13 13

N 1°21'19"E, 1368.10' rec. & meas.

Floyd & Peggy Jean Jones
Burgess & Laura L. Jones L.E.

N 1°21'19"E

1358.10' To RR Spk

165'
rec & meas

Some Fence Fd On This Line

Ref. To R.R. Spk.
24" Oak Stump With Fence In It. NW 12'

I Set A Railroad Spike On The N-S Property Line
But Since I Didn't Run The Sec. Line I Left The
Spike About 10 Feet North

I Certify This Survey To Be Correct To The
Best Of My Knowledge

William H. Long May 8, 1986

William H. Long R.S. 6505
13301 T.R. 503
Big Prairie, Ohio 44611

8 9
13 12